REVISED FINAL REPORT K-65 DECANT SUMP REMOVAL ACTION FEBRUARY 1993

02/01/93

DOE-FN/EPA 30 REPORT **REVISED FINAL REPORT**

K-65

DECANT SUMP TANK REMOVAL ACTION

February 1993

FERNALD ENVIRONMENTAL MANAGEMENT PROJECT

REVISED FINAL REPORT

K-65 DECANT SUMP TANK REMOVAL ACTION

FEBRUARY 1993

Submitted by:

Fernald Environmental Restoration Management Corporation Fernald Environmental Management Project 7400 Willey Road Fernald, Ohio 45030

TABLE OF CONTENTS	4149
EXECUTIVE SUMMARY	1
OVERVIEW	2
REMOVAL ACTION IMPLEMENTATION	5
SAMPLING AND ANALYSIS	7
HEALTH AND SAFETY PLAN	10
QUALITY ASSURANCE PLAN	12
REGULATORY CONCERNS	13
FUTURE ACTIVITIES	15
CONCLUSION	17
REFERENCES	18
TABLES	
TABLES TABLE 1: COMPARISON OF ANALYTICAL RESULTS	8
TABLE 1: COMPARISON OF ANALYTICAL RESULTS	9
TABLE 1: COMPARISON OF ANALYTICAL RESULTS	9
TABLE 1: COMPARISON OF ANALYTICAL RESULTS	9
TABLE 1: COMPARISON OF ANALYTICAL RESULTS TABLE 2: ADDITIONAL RADIONUCLIDE ANALYTICAL RESULTS TABLE 3: RADON GRAB SAMPLE SUMMARY	9
TABLE 1: COMPARISON OF ANALYTICAL RESULTS TABLE 2: ADDITIONAL RADIONUCLIDE ANALYTICAL RESULTS TABLE 3: RADON GRAB SAMPLE SUMMARY ATTACHMENTS	9 11
TABLE 1: COMPARISON OF ANALYTICAL RESULTS TABLE 2: ADDITIONAL RADIONUCLIDE ANALYTICAL RESULTS TABLE 3: RADON GRAB SAMPLE SUMMARY ATTACHMENTS ATTACHMENT A: PRELIMINARY ANALYTICAL RESULTS	9 11 A-1 B-1

ACRONYMS

AEA Atomic Energy Act

ALARA As Low As Reasonably Achievable

ARARs Applicable, Relevant and Appropriate Requirements

BMP Best Management Practices

CATEX categorical exclusion

CERCLA Comprehensive Environmental Response, Compensation, and Liability Act

CFR Code of Federal Regulations

DOE Department of Energy

DOE-FN Department of Energy-Fernald Office DOE-HQ Department of Energy-Headquarters

ETS Effluent Treatment System

FEMP Fernald Environmental Management Project FFCA Federal Facilities Compliance Agreement

FMPC Feed Materials Production Center

FR Federal Register

HEPA High Efficiency Particulate Air

NCP National Oil and Hazardous Substances Contingency Plan

NEPA National Environmental Policy Act

NPDES National Pollutant Discharge Elimination System

OEPA Ohio Environmental Protection Agency

OSHA Occupational Safety and Health Administration

OU Operable Unit

PACD Proposed Amended Consent Decree

RAWP Removal Action Work Plan

RCRA Resource Conservation and Recovery Act RI/FS Remedial Investigation/Feasibility Study

RSE Removal Site Evaluation RWP Radiation Work Permit

WEMCO Westinghouse Environmental Management Company of Ohio

USC United States Code

U.S. EPA United States Environmental Protection Agency

4149

One of the Remedial Investigation/Feasibility Study (RI/FS) identified operable units, Operable Unit 4 (OU4), at the Fernald Environmental Management Project (FEMP) includes the two K-65 Silos (Silos 1 and 2), the metal oxide silo (Silo 3), Silo 4, the K-65 decant sump tank system, and the potentially contaminated soils surrounding the waste storage silos. A Removal Site Evaluation (RSE) was generated by the Department of Energy (DOE) consistent with 40 CFR 300.410. It was determined by the DOE-Fernald Office (DOE-FN), as the lead agency at the FEMP, that a removal action was necessary to remove liquid from the K-65 decant sump tank. This removal action was conducted pursuant to the Consent Agreement under Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) 120 and 106(a) between the DOE and the United States Environmental Protection Agency (U.S. EPA).

The K-65 Decant Sump Tank Removal Action was implemented to protect human health and the environment from a potential release of the liquid within the decant sump to the surrounding subsoils. Pumping was initiated on March 26, 1991, and was completed on April 16, 1991, ten (10) days ahead of schedule. During this period, approximately 10,000 gallons of sump liquid were removed from the decant sump tank and access piping. Prior to treatment at the FEMP wastewater treatment facilities, samples of the liquid were taken and analyzed in accordance to FEMP hazardous waste management and control practices. On evaluation of the analytical results, it was determined that the liquid could be treated using approved treatment procedures for heavy metals and radionuclides at the existing FEMP wastewater treatment facilities. Treatment was completed on May 12, 1992. After treatment, the wastewater was discharged through a National Pollutant Discharge Elimination System (NPDES) monitoring point.

Rainwater infiltration into the decant sump system is expected to occur slowly over time. Therefore, post-removal action monitoring of the liquid level is required, as a best management practice action, until final remediation is initiated. Future removal of the liquid in the K-65 decant sump tank may be required based on the monitoring results.

OVERVIEW

W. . . .

The K-65 Silos are large concrete structures built in 1951 and 1952 which contain the residues from pitchblende ore processing operations at the Fernald Environmental Management Project, formally known as the Feed Materials Production Center (FMPC), and at St. Louis (Mallinckrodt Chemical Works). These residues contain radium, uranium, and thorium (Th-230). Beneath each silo, an underdrain system, which was designed to discharge into a sump tank, was constructed to collect drainage from the surrounding subsoils and any potential leakage through the concrete and clay base on which Silos 1 and 2 were constructed.

The silos were designed with a decant system which also discharged into the sump tank. The silos were filled by a process that consisted of pumping a slurry, settling of the solids, and decanting of the liquid, which was recycled. The decant system was designed to remove the liquid portion of the K-65 slurry after the solids had settled. Since this liquid was withdrawn in conjunction with the process of filling the silos, it was used on a daily basis during the years the silos were filled. As the primary purpose of the sump tank was to receive the liquid, it was called the decant sump tank. The decant tank has a 9,000-gallon design capacity.

Earthen berms were placed around the silos in 1964 to provide structural support to the silos. Berm construction was done in two phases. Due to the steep slope of the first berm, slumping occurred. A second berm was placed over the first to stabilize the berm slope. At this time, the decant system was disconnected from the decant sump tank since the silos were no longer being filled, but the underdrain system remained intact. The purpose was to continue to have the capability of collecting any drainage to the underdrain system.

Prior to the completion of the earthen berm addition, a 30-inch diameter corrugated, galvanized steel pipe was attached to the decant sump tank manway to provide access to the decant sump tank. This pipe was designed to extend upward 33 feet to the top of the berm. As a result of the slumping of the first berm, the access pipe shifted and bent. Although this pipe provided access to the decant sump tank, no information exists to indicate that the level of the liquid in the decant sump tank was monitored prior to August 1989.

In August 1989, a monthly sampling program was initiated at the request of the U.S. EPA. As a result of this sampling activity, high concentrations of radionuclides were observed in the decant sump tank liquid. The contaminants found in the decant sump tank were similar to those found in the K-65 Silo residue. These results supported the belief that the tank had not been cleaned of residues when the decant system was disconnected and the silo berms were constructed. The data from this sampling program was used to support the preparation of the RSE.

Concerned about a potential release and subsoil contamination, an RSE was prepared to support DOE-FN in the determination of the need for the removal of this liquid from the decant samp tank. In response to the RSE, DOE-FN issued an Action Memorandum to the operating contractor to implement a removal action.

A Removal Action Work Plan (RAWP) was prepared in accordance with the Consent Spreament. The Consent Agreement requires that a work plan be submitted to the U.S. EPA for review and approval prior to the implementation of all removal actions. The U.S. EPA conditionally approved the submitted RAWP on January 10, 1991.

Results from the October 1990 preliminary (pre-removal action) sampling of the decant sump tank liquid (this sampling effort is separate from the monthly sampling program initiated in August, 1989) were evaluated prior to the initiation of the removal action. The preliminary analyses results (Attachment A) indicated that the trace volatile organic compounds detected were below regulatory concern, however, measurable concentrations of some heavy metals and radionuclides were observed. Throughout the removal action, management and control of the potentially hazardous liquid was performed according to all applicable, relevant and appropriate requirements (ARARs) identified for this removal action, in conjunction with FEMP hazardous waste management practices.

The constituents that were observed in the decant sump tank are defined as "by-product" material and therefore are excluded from Resource Conservation and Recovery Act (RCRA) regulations under 40 CFR 261.4(a)(4). The pitchblende ore contained heavy metal impurities that were native to the different regions (i.e. the Belgian Congo, Australia) that supplied the ore to the FEMP. When processed, these impurities were liberated from the rock matrix of the uranium ore. These naturally occurring heavy metal compounds, containing arsenic, cadmium, chromium, lead, selenium, and silver, were removed from the process material and collected as a constituent of the slurried residue. The process residues that were in the decant sump tank contained these liberated process impurities.

During the implementation phase of the removal action, approximately 10,000 gallons of sump liquid were removed from the decant sump tank and access piping and ultimately transferred to the FEMP wastewater treatment facilities for treatment. In order to determine the proper disposition of the material, samples for final analyses of the pumped liquid were required to be taken. The pumped liquid was handled, stored in Plant 2/3 Refinery Tank F3E-408, and monitored, in accordance with hazardous waste management procedures. Final analyses (Attachment B) of the pumped liquid from the decant sump tank yielded results which showed that all volatile organics and semi-volatile organic compounds were below concentrations of regulatory concern, however, a number of heavy metals were present, as "by-product" residue impurities, in levels exceeding the regulatory limits.

Meeting the FEMP wastewater pre-treatment standards (e.g. volatile organic or semi-volatile organic constituents at levels below regulatory concern), the liquid was treated in the existing FEMP wastewater treatment facilities using approved treatment procedures for heavy metals and radionuclides. After treatment, the wastewater was discharged through an NPDES monitoring point. This treatment was completed on May 12, 1992.

As a follow-up to the removal action, the level of the liquid in the decant sump tank has been measured on a routine basis to observe the expected rainwater infiltration into the decant sump tank system. Approximately one (1) year after the completion of the removal action, the liquid

level in the decant sump tank had risen approximately three (3) feet. This corresponds to approximately 3,000 gallons of liquid and sludge. These results were expected as the underdrain system is still intact. The monitoring of the decant sump tank liquid will continue until final remediation.

The point at which further pumping of the liquid in the decant sump tank should be initiated to prevent potential release of the liquid into the environment has been estimated, using best engineering judgement, to be in the order of 75 to 80% of the 9,000-gallon tank capacity.

In December 1992, the level in the tank was calculated to be within the 70 to 80% target range. A planned maintenance operation was implemented to remove the liquid in the decant sump tank in accordance with the procedures outlined in the K-65 Decant Sump Tank RAWP.

REMOVAL ACTION IMPLEMENTATION

In 1964, the decant portion of the system was disconnected in conjunction with the placement of the earthen berms around the silos, but the underdrain system was left intact. This underdrain system was designed to collect potential leakage from the K-65 Silos or drainage from rainwater and groundwater infiltration. The collected liquid from the underdrain system is delivered to the decant sump tank via underground pipe. Also at this time, access was provided to the decant sump tank by attaching a 30-inch diameter corrugated galvanized steel pipe to the manway of the decant sump tank. The pipe extends 33 feet upward to the top of the berm. This access pipe was bent by slumping of the earthen berm from 1964 and therefore currently provides only limited access for monitoring.

During the routine monthly sampling of the decant sump tank (initiated in August of 1989), standing water was observed inside the corrugated galvanized steel pipe, approximately 25 feet above the decant sump tank. Concerned about a potential release and subsoil contamination, the DOE-FN initiated an RSE.

Consistent with Section 300.415 of the National Oil and Hazardous Substances Contingency Plan (NCP), two factors were presented in the RSE for DOE-FN to consider in determining the appropriateness of such a removal action.

- 1) Actual or potential contamination of drinking water supplies or sensitive ecosystems.
- 2) Hazardous substances, pollutants or contaminants in drums, barrels, tanks, or other bulk storage containers, that may pose a threat of release.

On completion of their review of the RSE, DOE-FN as the lead agency, determined that the removal of liquid from the K-65 decant sump tank was an appropriate time-critical removal action which followed the guidelines of the NCP. On August 24, 1990, DOE-FN issued an Action Memorandum which directed that a RAWP be prepared in accordance with the Consent Agreement. The Consent Agreement requires that a work plan be submitted to the U.S. EPA for review and approval prior to the implementation of each removal action. The U.S. EPA conditionally approved the DOE-FN submitted RAWP on January 10, 1991.

The scope of the K-65 Decant Sump Tank Removal Action consisted of removing the liquid from the K-65 decant sump tank, dispositioning the removed liquid, and treating of the liquid at the existing FEMP wastewater treatment facility. Management and control of the liquid was in accordance with the FEMP radiological and hazardous waste management practices.

The work plan identified the support activities which included the planning activities, the additional data/studies, the design activities, and the training requirements that were necessary to perform the removal action. Field actions were outlined to direct the implementation of the removal action and the treatment process.

During the implementation phase of the removal action, approximately 10,000 gallons of sump liquid, taken from the decant sump tank and access piping by a submersible pump, was collected by a tank-trailer and transported to the FEMP wastewater treatment facilities for eventual treatment. Multiple trips to the treatment facility were required to be taken by the 5000-gallon capacity tank-trailer. A representative sample of the liquid for each load of liquid transferred was taken from the tank-trailer to analytically test for organics, heavy metals and radionuclides prior to wastewater treatment. Approximately 300 gallons of residue sludge, which originated from the original decant operations, is estimated to remain in the decant sump tank itself.

The results of both the pre- and post-removal action analyses yielded trace volatile and semi-volatile organic compounds at levels below regulatory concern. Measurable concentrations of the radionuclides isotopes uranium, radium, thorium, and lead were observed in the samples. These are the same radionuclide constituents that exist in the residues that are contained in the K-65 Silos. Detailed information on the analysis results is included in the Sampling and Analysis section.

FEMP pre-wastewater treatment does not allow volatile or semi-volatile organics to be present at levels above regulatory concern in FEMP wastewater prior to treatment in the wastewater treatment facility. Since volatile and semi-volatile organics were present at levels below regulatory concern, as seen by the results of the post-removal action analyses, wastewater treatment for radionuclides and heavy metals was allowed. The treatment process for radionuclides and heavy metals in the wastewater treatment facility was largely determined by the presence and content of Thorium in the wastewater to be treated (refer to Section IV, 2.0, page 6 of the RAWP).

The pumped liquid that was stored in Plant 2/3 Refinery Tank F3E-408 was neutralized and transferred by pipeline to the Plant 8 wastewater treatment facility. Solids were removed from the wastewater by filtration. The filtrate was pumped to the General Sump and segregated for nitrate treatment. The filtrate was then pumped to the Biodenitrification Surge Lagoon where additional solids removal by settling occurred. The filtrate was then pumped into the Biodenitrification Bioreactors for nitrate reduction.

Meeting the FEMP wastewater discharge standards, the filtrate was discharged to the Effluent Treatment System (ETS) for Biological Oxygen Demand and Total Suspended Solids control. It should be noted that the wastewater treatment for radionuclide removal is effective for all types of radionuclides, including the minute amount of Radium-226 detected by the pretreatment, post-removal action sampling and analyses. The treated filtrate was then discharged from the ETS through a NPDES monitoring point, which is monitored routinely.

SAMPLING AND ANALYSIS

Starting in August 1989, the liquid in the corrugated pipe above the decant sump tank was sampled and analyzed by FEMP personnel for radionuclides in order to support the development of the RSE. In addition, preliminary (pre-removal action) sampling and analyses were conducted in October 1990 to support the health and safety controls in the RAWP. The preliminary sampling analyses results are included as Attachment A. During the removal action (post-removal action), a representative sample from each load was taken from the tank-trailer prior to transferring it to Plant 2/3, where the liquid was stored in the Refinery Tank F3E-408. The sampling analyses results for each of the representative samples are included in Attachment B. The pumped liquid remained in storage until the sampling analyses results became available. An independent laboratory was used to support this phase of the work.

A comparative analyses of the pre-removal action, post-removal action, as well as the analytical results from the K-65 materials themselves are shown in Table 1. Comparative analyses of results of these waste streams can be used for identification of material origin. As is evident in Table 1. results from the pre-removal action sampling analyses (Attachment A) and the post-removal action sampling analyses (Attachment B) show that the radionuclide and heavy metal constituents in the liquid are similar to those seen in the K-65 residue. Furthermore, comparison of the results from the analyses of decant sump tank sludge (denoted by an "*" on Table 1) to the results of analyses of the K-65 residue (solid) shows that the decant sump tank sludge contains the same radionuclide constituents at concentration levels within the range observed for the constituents in the K-65 residue.

The preliminary pre-removal data was included solely for background information only. It was used as a basis for determining the health and safety requirements for handling the decant sump tank liquid. It should be noted that using these data for comparison is not relevant due to the fact that the pre-removal data were not validated by the laboratory that performed the analysis.

The types of radionuclides found in the decant sump tank were similar to those found in the K-65 residue. The maximum concentrations of the primary radionuclides of concern, as determined by sampling analysis, are: U-238 (26,000 pCi/L), U-234 (139 pCi/L), Ra-226 (1,200 pCi/L), Th-230 (<1 pCi), and Pb-210 (8,000 pCi/L). Consistent with the State of Ohio Proposed Amended Consent Decree (PACD), process residues found in the decant sump tank are by definition "by-product" material and therefore are excluded from RCRA regulations under 40 CFR 261.4(a)(4).

As requested by the Ohio Environmental Protection Agency (OEPA), DOE-FN performed analyses on the decant sump tank liquid for the additional radionuclides: actinium-227, protactinium-231, polonium-210 and lead-210. Due to the timing of the request relative to the progress of the post-removal action lab work, only a limited analyses for the additional radionuclides were possible. The results are listed in Table 2.

TABLE 1
COMPARISON OF ANALYTICAL RESULTS

Constituent	Attachment A Decant Sump Tank (Liquid)	Attachment B Decant Sump Tank (Liquid/Sludge*)	Analysis of K-65 Silo Residue (Solid)
Total Uranium	57500 ug/l	77400 ug/l < 1255 ug/g	137-<18117 ug/g
Thorium 230	358 pCi/l	16 pCi/l 52130 pCi/g	20500-160000 pCi/g
Radium 226	557 pCi/l	1640 pCi/l 128500 pCi/g	657-890700 pCi/g
· Arsenic	855 ug/l	720 ug/l	3.1-1960 mg/kg
Barium	683 ug/l	66 ug/l	89-22100 mg/kg
Cadmium	28 ug/l	14 ug/l	0.42-19.1 mg/kg
Chromium	417 ug/l	454 ug/l	12.9-165 mg/kg
Lead	39000 ug/l	627 ug/l	153-299000 mg/kg
Mercury	0.2 ug/l	0.2 ug/l	0.09-2.8 mg/kg
Selenium	5530 ug/l	7270 ug/l	0.32-2810 mg/kg
Silver	182 ug/l	230 ug/l	1.8-34.9 mg/kg

Note 1: (*) indicates the sample media was sludge.

TABLE 2
ADDITIONAL RADIONUCLIDE ANALYTICAL RESULTS

Boring # Sample # Media Type Units	K-65 D 099416 liquid pCi/l	K-65 D 099417 sludge pCi/g
Actinium-227 Protactinium-231 Polonium-120 Lead-210	<91.1 <431 7080 8660	5783 < 855 n/a 123200

Sampling of both the wastewater during treatment, and the effluent discharged after treatment, was performed in accordance with the K-65 Decant Sump Tank Removal Action ARARs, FEMP policy and procedures, the FEMP Federal Facilities Compliance Agreement (FFCA), and the FEMP NPDES Permit. All regulatory limits for wastewater discharge were met.

HEALTH AND SAFETY PLAN

The task-specific Health and Safety Plan. which was prepared for implementation of this removal action, was designed to protect personnel working under the Radiation Work Permit (RWP) from excessive exposure to both the penetrating radiation and the airborne particulate radiation found in the vicinity of the K-65 Silos. The penetrating radiation dose was determined to be in the range of 50-60 mrem/hr on the K-65 berm near the top of the corrugated pipe to about 0.6 mrem/hr at the inside of the fence to the west of the sump. The highest radiation readings in the area were 150 mrem/hr on contact with the silo domes. Furthermore, Radon from the K-65 Silos was identified as the constituent that exhibited the highest potential for personnel exposure.

An Exclusion Zone was established to demark the area of high potential hazard from radiological or chemical dangers. Access to the Exclusion Zone was restricted to trained and certified employees as required by OSHA 29 CFR 1910.120. Personnel stay-times in the K-65 Area were controlled by radiological safety procedures to ensure that personnel did not exceed the site administrative exposure control level of 150 mrem/week.

Air monitoring, targeted in the breathing zone, assured that contaminant concentrations did not exceed the concentrations specified by allowable exposure levels. The air monitoring program was designed to detect radon and radon progeny. Continuous radon gas monitoring was provided at the K-65 Area fenceline using alpha scintillation devices. Working level grab samples (Table 3), designed to detect radon progeny, were collected by a portable air pump and filter unit (breathing zone monitor). Working level concentrations are exposure concentration estimates for personnel working in the immediate area.

Radiation surveys were conducted at the beginning of the work. Personnel were required to wear direct reading dosimeters and to monitor radiation exposure periodically. Particulate radionuclides from the liquid were prevented from becoming airborne by use of High Efficiency Particulate Air (HEPA)-filtered vents on the receiving tanks. Monitoring was performed to ensure that personnel were not excessively exposed above the allowable weekly dose.

All site personnel were trained in accordance with OSHA 29 CFR 1910.120, as well as, Westinghouse Environmental Management Company of Ohio (WEMCO) and DOE-FN site requirements.

TABLE 3

RADON GRAB SAMPLE SUMMARY

DATE	LOCATION	WORKING LEVEL	COMMENTS
06/26/91	Decant Sump Manway	0.199	None.
06/26/91	Decant Sump Manway	3.95	None.
06/19/91	Decant Sump Tank Valve	0.0001	Post Sampling Air Check.
06/19/91	Downwind of Decant Sump: Hatch of Tanker Truck	0.0001	Sample taken at hatch of tank truck while pumping.
06/18/91	Weston Road: Hatch of Tanker Truck	0.112	Sample taken at hatch of tank truck while pumping.
06/18/91	Top of Decant Sump Tank	8.87	None.
06/18/91	Weston Road: North of Silo 1	0.075	Downwind of decant sump tank area.
06/18/91	Downwind of Decant Sump: Hatch of Tanker Truck	0.031	Taken within Exclusion Zone while pumping.
06/07/91	Decant Sump Area	0.287	None.
05/14/91	Decant Sump Tank Manway	5.138	None.
04/16/91	Downwind of Decant Sump Manway	0.007	None.
04/16/91	Tanker Hatch: East of Pressure Gauge	0.19	None.
04/16/91	Decant Sump Tank Manway	3.83	None.
04/16/91	Tanker Hatch: West of Silo 1	1.93	None.
04/16/91	Decant Sump Tank Manway	5.36	None.
04/16/91	RGM #2: Tanker Work Area	Not Detected	None.
04/16/91	Left Rear Truck Bumper: Work Area	Not Detected	None.
04/16/91	Van: 25' South of Tanker Work Area	Not Detected	None.
04/16/91	Ledge, Below Vent of Decant Sump	0.014	None.
04/16/91	4' North of Decant Sump Manway	1.62	None
04/16/91	4' North of Decant Sump Manway	0.082	None.

QUALITY ASSURANCE PLAN

The K-65 Decant Sump Tank Removal Action was conducted in accordance with the requirements of the overall quality assurance program at the FEMP which is described in the site Quality Assurance Plan, FMPC 2139. The Quality Assurance Plan is based on the criteria specified in ASME NQA-1, Federal EPA Guideline QAMS-005/80, and DOE Orders 5700.6 and 5400.1. Specific quality assurance requirements were incorporated into written and approved procedures and into personnel training. Periodic surveillance reports, performed by the FEMP operating contractor, verified that implementation of the K-65 Decant Sump Tank Removal Action complied with the Quality Assurance Plan.

REGULATORY CONCERNS

The contents of Silos 1 and 2 are exempted from RCRA regulation by the OEPA in 40 CFR 261.4(a)(4), which exclude "by-product" material as defined by the Atomic Energy Act (AEA) of 1954, as amended, 42 USC 2011 et seq. (AEA). The material stored in the K-65 Silos are tailings and/or residues produced by the extraction of uranium (10 CFR 962, 52 FR 15937) and therefore meet the exclusion by definition.

The exclusion, according to 40 CFR 261.4 (a)(4), applies to "...source, special nuclear or "by-product" material as defined in the ...[AEA]...". The AEA defines "by-product" as:

"...(1) any radioactive material (except special nuclear material) yielded in or made radioactive by exposure to the radiation incident to the process of producing or utilizing special nuclear material, and (2) the tailings or waste produced by the extraction or concentration of uranium or thorium from any ore processed primarily for its source material content" [AEA Section 112(e)].

The material stored in the K-65 Silos is residue resulting from the processing of uranium ore. Under 40 CFR 261.1(a)(4), as applied here, the residues in the K-65 Silos are excluded from regulation under RCRA as the residues resulted from the processing of uranium ores, and are not "... "by-products" from utilizing special nuclear material...". In addition, "by-product" material is expressly excluded from the definition of solid waste under federal law [40 USC 6903(27)].

The residue material present in the decant sump tank is from past decanting operations of the K-65 Silos. During the original placement of the K-65 Silo material, slurried liquid was decanted from the silos into the decant sump tank. K-65 residue in the form of suspended solids, present in this decanted liquid, settled to form the residue material in the decant sump tank. Approximately 300 gallons of this residue material, originating from K-65 Silo decanting operations, currently remains in the decant sump tank. This residue, a "by-product" material by definition, is excluded from RCRA. Any liquid which accumulates in the tank is therefore mixed with this "by-product" material, and is itself excluded from RCRA. This interpretation is consistent with EPA guidance for residual water and runoff from coal ash which is also excluded from regulation in 40 CFR 261.4. The sentiment indicated by this guidance is that residuals generated from an excluded material can themselves be excluded.

The K-65 decant sump tank is still connected to an active underdrain system located below the K-65 Silos. Although this tank served to receive decant water from the residues slurried into Silo 1 and 2 (K-65 Silos) during the Silos' operational period, a secondary function of the tank was to contain any liquids collected below the base of these silos by the underdrain system. The decant sump tank continues today to act as a means to manage rainwater infiltration of subsoils beneath the silo base.

In conclusion, the rainwater infiltration into the tank is contaminated by K-65 residue sludge, a "by-product" material that is currently in the decant sump tank, and is therefore excluded from regulations under RCRA according to 40 CFR 261.4 (a)(4).

To support waste management activities, a list of potential ARARs (Attachment C) for he removal action was developed because the material exhibited the potential for heavy metal in quantities in excess of RCRA levels. Meeting the FEMP wastewater pre-treatment stantages (e.g. volatile organic or semi-volatile organic constituents below levels of regulatory concurn), the liquid was treated in the existing FEMP wastewater treatment facilities using approved treatment procedures for heavy metals and radionuclides. The NPDES regulatory requirements for FEMP wastewater discharge were met by the proper storage, treatment, and disposal activities performed in accordance with the requirements of CERCLA and DOE orders and procedures.

To fulfill the requirements of the National Environmental Policy Act (NEPA), a categorical exclusion (CATEX) determination was generated and approved by DOE-Headquarters (DOE-HQ). The CATEX was prepared in accordance with the September 7, 1990, Section D Amendment to the NEPA. Under this September 1990 amendment, removal actions under CERCLA do not require Environmental Assessments or Environmental Impact Statements. Prior to generating the Categorical Exclusion Determination, it was determined that this project did not threaten a violation of applicable statutory, regulatory, or permit requirements and that it would not affect "environmentally sensitive areas".

FUTURE ACTIVITIES

The decant sump tank itself is capable of holding 9,000 gallons. The 33-foot, 30-inch diameter corrugated, galvanized steel pipe, welded onto the top manway access of the decant sump tank prior to placement of the earthen berm around the silos, and the associated piping of the underdrain system is estimated to hold at least 1,000 gallons. From observation of the presence of standing liquid in the access pipe prior to implementation of the removal action, it is logical to assume that the tank and access pipe system are essentially intact and capable of holding 10,000+ gallons.

The K-65 Decant Sump Tank Removal Action was originally initiated to reduce the risk associated with decant sump tank liquid release during the K-65 slant boring activities required in the K-65 decant sump tank area. This sampling program revealed that high concentrations of the major constituents of the K-65 residues (i.e. Th-230, Ra-226, Pb-210) were not evident in the perched groundwater near the decant sump tank. In addition, periodic measurements of the tank's water level have revealed that the water level is increasing, most likely due to the infiltration of rainwater into the underdrain system. Both of these facts support the hypothesis that leakage from the tank is minimal.

Being an "active system", the decant sump tank is expected to collect liquid as it has in the past and will continue to in the future. Future planned work activities focus on the monitoring of the level of liquid in the K-65 decant sump tank.

Based on best engineering judgement, the point at which further pumping of the liquid from the decant sump tank should be initiated to prevent release of the liquid into the environment has been estimated to be in the order of 75 to 80% of the 9,000-gallon tank capacity. This target level allows for time to implement the maintenance activity of pumping the tank (it would not be sensible to wait until the tank reached its full capacity before implementing the maintenance activity due to the possibility of unforeseen delays). Future pumping at the 75 to 80% tank capacity also makes sense from an As Low As Reasonably Achievable (ALARA) standpoint. More frequent pumping would create unnecessary risk from the repeated exposures associated with the handling and processing of small batches of liquids.

Routine decant sump liquid level measurements have been made by the FEMP since the removal action was completed. Rainwater infiltration into the decant sump system is expected to occur slowly over time. The sump level had increased a total of 33.8 inches from June of 1991 to August of 1992; with a 27.8 inch increase between February and August of 1992. Between June 1991 and December 1992, measurements indicated that the water in the decant sump tank increased a total of 72.9 inches.

In December 1992, the level in the tank was calculated to be within the 70 to 80% target range. A planned maintenance operation was implemented to remove the liquid in the decant sump tank in accordance with the procedures outlined in the K-65 Decant Sump Tank RAWP. The removed liquid was then managed in accordance with the existing procedures and ARARs as outlined in the RAWP.

Consistent with the goals of OU4 Final Remediation, periodic maintenance pumping actions will mitigate the threat of overfilling the decant sump tank and the potential release of liquid to the surrounding environment. Periodic monitoring will be performed until final remediation of the system is implemented. As the liquid in the decant sump tank again approaches 75 to 80% of the tank's capacity, periodic maintenance pumping activities are planned and will be implemented in accordance with the procedures outlined in the K-65 Decant Sump Tank RAWP. Also, if an abnormal event (i.e. a sudden drop in liquid level which would indicate a loss of tank integrity) occurs, an immediate evaluation would be made to determine whether pumping of the remaining liquid should be implemented.

CONCLUSION

4149

The K-65 Decant Sump Tank Removal Action successfully implemented an action to protect human health and the environment by mitigating the threat of a potential release of radiologically contaminated liquid to the subsoil in the area adjacent to the FEMP K-65 Silos. The K-65 Decant Sump Tank Removal Action followed an approved work plan that outlined the planning and design requirements, the removal action implementation, the sampling analysis requirements, the health and safety procedures, and the quality assurance objectives. The decant sump tank, associated equipment, and any residues will be dispositioned as part of the final remediation of OU4.

In December 1992, the level in the tank was calculated to be within the 70 to 80% target range for repumping. A planned maintenance operation was implemented to remove the liquid in the decant sump tank in accordance with the procedures outlined in the K-65 Decant Sump Tank RAWP.

Because the liquid level in the decant sump tank is expected to be steadily increasing, post-removal action monitoring of the liquid level is required as a best management practices (BMP) action until final remediation is initiated. Future removal of the liquid in the K-65 decant sump tank may still be required based on the monitoring results. If the tank again approaches a full condition, defined as 75 to 80% capacity, prior to remediation, or, if an abnormal condition in tank level is observed, an evaluation of the condition will be made, and a recommendation will be forwarded to DOE-FN to authorize implementing any recommended actions.

REFERENCES

A copy of each document associated with the K-65 Decant Sump Tank Removal Action has been compiled and placed in the FEMP Administrative Record, under the title, "Removal Action #5 - Decant Sump Tank". A copy of Removal Action #5 index for the Administrative Record is included as Attachment D.



4149

ATTACHMENT A

PRELIMINARY ANALYTICAL RESULTS

K-65 DECANT SUMP TANK REMOVAL ACTION

RADIOLOGICAL QUALIFIERS

- D = Denotes possible false negative, i.e., the reported nonpositive value is greater than the CRDL.
- C = Denotes calculated total uranium value from uranium isotopic results does not agree within 20% of the reported uranium results.
- E = Denotes calculated enrichment of uranium 235 outside of acceptance limits.
- F = Denotes calculated uranium 234/uranium 235 ratio is outside of acceptance limits.
- J = Denotes analyte present, reported value may not be accurate or precise.
- M = Denotes matrix spike recovery out of bounded limit.
- R = Denotes that the results are unusable.

INORGANIC QUALIFIERS

- U = Analyte was analyzed for but not detected.
- J = Indicates an estimated value.
- B = Reported value was obtained from a reading that was less than the Contract Required Detection Limit (CRDL) but greater than or equal to the instrument Detection Limit (IDL).
- E = The reported value is estimated because of the presence of interference.
- N = Spiked sample recovery not within control limits.
- S = The reported value was determined by the Method of Standard Additions.
- W = Post-digestion spike for Furnace AA analysis in not out of control limits (85-110%), while sample absorbance is less than 50% of spike absorbance.
- X = Detection limit is higher than normal due to sample matrix interferences.
- = Duplicate analysis not within control limits.
- R = Denotes that the results are unusable.

ORGANIC QUALIFIERS

- U = Indicates compound was analyzed for but not detected. The sample quantitation limit must be corrected for dilution and for percent moisture.
- J = Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds were a 1:1 response is assumed, or when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the sample quantitation limit but greater than zero.
- B = This flag is used when the analyte is found in the associated blank as well as in the sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action.
- E = This flag identifies compounds whose concentrations exceed the calibration range for the GC/MS instrument for that specific analysis.
- D = This flag identifies all compounds identified in an analysis at a secondary dilution factor.
- F = Estimated value due to a confirmed compound which is offscale in both columns.
- X = A flag that FORMASTER III CLP software automatically inserts to indicate that the data was entered manually.
- * = Values outside of contract required QC limits.
- R = Denotes that the results are unusable.

CO 16 190 11:13 - 491 FERMALD

457 585

المرقد الجيدين

CENT 2011- CENT CENT


:::-\S-#0 E:277**

U.S. EPA - CLP

S SOCKIE

عد	Name:	IT_OAK_?	RIDGI	Contract:	PERNALD_		
طعة	Cada:	IIIML_	Case No.: 16377	:.ok EK8		SDG No.:	99403_
PES	aratic	m Blank	Matrix (soil/water): WAS	TER			
Preș	paratio	n Blank	Concentration Units (19,	/L or =9/kg): US/L_		

Analyte	Initial Calib. Blank (ug/L)	c 1	Continu Bl. C	ing Calib anx (ug/I 2	ration .) C	3	- - - - - - - - - -	repe- ation lank C	,
Museum	90.5		60.5 (0)	60.0	101	60.0	ai !	60.510	15
	30:6-		30.0-101	30.0	- 0		ği I	-10.01UI	ם ו
Yutrzouh_	:		50.0-101	30.0	10			_50.0 i Ti	7
Arsenic Barium	32:5-	<u> </u>	2.0-101		· ŭ		#i	- 2.01 0 1	P
		i 0 i	-2.0-101		10				פו
Berylline	·		-2.0-i0i		- 6		6i	2. 6 i u i	15
Cromins	:		70.a- U	20.0	-i 8		<u></u> ان		15.
Careran _	20.6	: #I —			· ŭ		oi	10.0101	P.
C22527.77		<u></u> ان	B	 ::::::	-		31	-10.5/8/	i >
Cobalt	::		יוטור ביים ביים	 -:::::	· i ŭ i		ői	- 12.01UI	15
Cepper			** %-1%1.		- ĕ		<u> </u>		P
Iron			*** %-141.		- 5		<u> </u>	-40.0101	13
Lead	40.c		40.0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		·			30.0101	15
Magnesium								— 3.0 i wi	P
Manganese	1 2 . 0		-4.5-10		-}	_***-	~	-0.21 0 1	1
(GICTITY	·			20.0	-101	28.8	01	- 10.0 i u i	P
Hickel	20.5		30.0_ U .	 100.0-			ان ^ن	Tag.aiu:	13
P021881==			00.0_ 0				—— اق	- 80.0101	Î
Selenium_	!80.S		86.0	80.0			#		P
Silver	10.0		10.0	10.0			· .	100.0101	15
Sod1u=	:::::::::::::::::::::::::::::::::::		55.5_ 2],	I00.0]		Ico.o]		2.0101	1
mal:	[<u></u> :.:		_2.0_ 0			 ;	,, i		İ
Vanadium_	<u> </u>			10.0	וט .		<u></u> اات		
Z435	: <u></u>	: o i	_3.0_[0]	5.0			<u> </u>	5.0!!!	17
Cyanica	:::-	[T]	_2.0_[U]	2.0_	0	2.0_]:			Į A.



::-15-73 5:27-4 :

; = 3

J.S. 27A - CLP

INCRGANIC ANALYSES DATA SHFFT 99403 Name: IT_CAK_RIDGE	²
MACTIC CASE NO.: J6377 SAS NO.: SDG NO.: 99 MACTIC (Scil/Water): WATER Lab Sample ID: FF 254 Date Received: 11/01/ Solids:	²
Matrix (scil/water): WATIR Lab Sample ID: FT 254 Lab Sample ID: FT 254 Lab Sample ID: FT 254 Cate Received: 11/01/ Concentration Units (uq/L or mg/kg dry weight): UG/L Cas No. Analyts Concentration C Q X 7440-36-0 Antimony 159 2 7440-38-2 Arsanic 855 2 7440-39-3 Barium - 683 2	²
Cas No. Analyts Concentration C C X CAS No. Analyts Concentration C C X 7425-90-5 Aluminum 16200 P 7440-38-2 Areans 855 P 7440-38-3 Barium - 683 P	
CAS No. Analyte Concentration C C X 7425-90-5 Aluminum 16200 P 7440-36-0 Antimony 1591 P 7440-38-2 Arsenic 855 P 7440-38-2 Barium 681	9 0
CAS No. Analyte Concentration C C X 7425-90-5 Aluminum 16200 P 7440-38-2 Arsenic 855 P 7440-38-3 Barium 681	
CAS NO. Analyts Concentration C X	
CAS No. Analyts Concentration C X	
CAS No. Analyte Concentration C C X 7425-90-5 Aluminum 36200 P 7440-36-0 Antimony 1891 P 7440-38-2 Arsanic 855 P 7440-38-2 Arsanic 855 P 7440-39-3 Barium 683	
7429-90-3 Aluminum 36200	
7429-90-3 Aluminum 36200 P- 7440-36-0 Antimony 1891 P- 7440-38-2 Arsanic 855 P- 7440-39-3 Barium 681	
7440-36-0 Antimony 1691 P 7440-38-2 Arsanic 6831 P 7440-39-3 Barium 6831 P 7440-39-3 P 7440-39-3	
7440-36-0 Antimony 1691 P- 7440-38-2 Arsanic 8551 P- 7440-39-3 Barium 6831 P-	
7440-38-2 Arsanic 855	
7440-19-1 BEF1UE 0831 151	
7440-41-7 Beryllium	
7440-43-9 Cadmium 28.47 -;	
7440-70-2 Calcius 236000	
19440-47-3 (CT-001115) 417	
7440-48-4 CODE12 1560 P	
7440-50-8 Copper 887 P	
701001	
7439-92-1 Lasd 390001 P	
7439-95-4 Magnesium: 372001 P	
7439-96-4 Mangapese 16201	
7439-47-6 Marrier 0.281U CV	
7440=02=0 Nickel 2330	
7440-08-7 PARRELUE! 18000 A	
7782-49-2 Selenius \$530 P	
7440-23-4 godina 100 U P	
7440-43-2 Vanadium 511	
7199	
Cyanics 462 AB	
lor Before: GREEN Clarity Before: OFAQUE Texture: N	/ \ _
Clarity After: CIAR Artifacts: Y	<u> </u>
COLUMN TERES YELLEN CLERTY After: CLEAR AFTIFICES: Y COMMENTS: CRASS AND EUGS WERE PRESENT IN SAMPLE. SAMPLE WAS FLUCKESCENT GREEN PT 2542 FOR MG IS THE SAME AS FF 2543. TT 2551 FOR CN IS THE SAME AS FF 2543.	

100 18 198 10:1⁷

ra: razyrent

EE7 =23

33339-esi

;= 2

ITAS-KW09	BR 01		Tr. Con	KATRI	Page of	~
FROIZOT C	EDE: ADV 3	36577		DATE RECEIV	m: 11/01/00	·
SNOPLE DE	SCRIPTION:	(45 Decan	Tank	CHCENTURI	ON CHITS:	_
CLIMT #:	dance					
SAMPLE #:				•		
NH3, TON.	PO, == 75	4	-		 .	-
C1, F1, S	o, <u>FF 754</u>	<u> </u>	· · ·	_	-	
HO; / PHEN	or ff <u>iski f</u> f	75W				
SULTIDE	FF254	<u> </u>				- Control of the last of the l
TOC	FF25	<u> </u>			-	
TOX	FF:	<u> </u>	- · 			:====
						معتنق
		_	PREUL			
	Pres Cata	Anal Care	BLANK	09403		
ADCONIA	TOBAC	11 /08/90	0.10 U	12.6		
TON	_''	11,09,90				آند.
TL. PHOS.	11/11/20	T-11-40	0.0211	8.13	· · · · · · · · · · · · · · · · · · ·	
CELERIEZ .	11 ,09,00	11,09,90	<u>0.55 U</u>	90.9		
FLUCRICE	11 114 20	11/14/40	0.10 LL	18.7		3
SELFATE	11/17/90	11/12/40	2.00 U	<u> </u>		
HITRATE	11,07,90	下面る	<u> </u>	381		
PRIMOL			0.01 W			
SULFIDE		11,05.90				
700		11 /07/90				<u> </u>
TOX	17 02 \ 40	11/08/90	<u>0.01011</u>	<u> </u>		
RIVITWED 8	Y:		REVI	2002 8X:	<i></i>	

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

99403R

EPA SAMPLE %

Contract: àDY Lab Name: TAS-OAK RINGE

Matrix: (soil/water) WATER FF75528

Lab File II: 1000 (g/mL) KI Date Received: 11/01/90 sample we/vol:

(low/med) tow

Date Extracted: 11/15/90 Level: 12C. ____

₹ Molsture: not dec. ___ Date Analyzed: 11/19/90

Extraction: (Sepf/Cont/Sonc) SEPF Dilucion Factor: 1.0 pH: ____ GPC Cleanup: (Y/N) Y

CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L

Number TICs found: _____

Number TICS Tours			ESTCONC	. Q
= = = 17-B	COMPOUND NAME PHOSPHORIC ACID TRIBUTYL EST S-INDACINE-1,7-DIONE, 2,3,5, UNKNOWN DECANE, 2,4,6-TRIMETHYL-	17.44	140 11 6.2 4.6	3 3 3

457 994 CU 16 70 11:15 := 5 :::-19-45 S:23FM : TESTS-LST FERNALS SENT BY: IT CERT CT. 0000 IFA SAMPLE N. "CLICIL CRGANICS ANALYSIS DATA SHEET 99402 Lab Name: TTAS-OAK RITGE Contract: ADV Lab Cade: : ----Case No.: 15151 SAS No.: HA SDG No.: 99402 Matrix: (soil/vatar) Where Lab Sample ID: -1.6 (g/ml) XI Sample we/wol: Lab File ID: 777777 LCM (Lov/Esd) Cats Received: 12/75/90 Date Analyzed: 4 Moisturs: not dec. 10/29/90 Action: (pack/cap) PACK Dilution Factor: 1.1 CONCENTRATION UNITS: CENTROTHE CAS NO. (ug/L or ug/Kg) CG/L 2 · • 74-67-3--Chicremethane 10 U 10 U -Vinyl Chloride 10 U Chicrosthene 75-00-1--18 U 75-09-2---- Methylene Chlerics 6 1 -ACREORS 67-64-1---16 3 Carpon Disulfide 75-15-0-J -1.1-Dichloroethene U 75-35-4---1,1-01chiorcethane 75-34-3--10 -1.2-Dichigroethene (total) 540-59-0-U -culorotors 67-66-3--5 -1,2-Dichlorostnans 5 U 107-06-2---------13 78-93-3---13 -1,1,1-TT:CRIOTOGERANG 10 71-55-6--5 Ü -Carron Tatrachlerade 56-23-5-200 -Vinyi Acetsta 108-05-4--dremedichieremennane 75-27-4----1,2-Dichlerepropane J 78-47-5--cis-1.1-Dichieropropene 10061-01-5-5 -Trichleroethene 79-01-6--U Oibromochioromethane U 124-48-1--1,1,2-Trichloroethane 79-00-5-U U -tensane 71-43-2-90 -Trans-1, 1-01chloropropene 5 10061-02-4-75-25-2--truncters 13 108-10-1----- Metryl-1-Pentanone 40 10 -1-Herranene 551-78-4--Tetrachlorostnane 5555 127-18-4--Gaal -1,1,2,2-Tetrachlorosthane 79-34-4-108-48-3---Toluene -Chloropensene 158-90-7---200 -ithylbensene 100-41-4---- Styrene 100-42-5--1220-20-7------ POESL XYLANGS

1/87 Rev

بالمرابع

557 787

45; FER!44L3

:::-:5-50

2532-431 FEMILE

:= 4

Z CREANICS ANALYSIS DATA SHEET

99402

00006

Lab Mane: The-Oak River Case No.: 15151 Lab Code: **-WVL

אווסוסוונט

DRIGHT

Contract: ADV SAS No.: XA

SDG No.: 99402

11

Matrix: (soil/water) Where

Lab Sample ID: 777161R Lab File ID:

Sample we/wol:

프라 카: (T 대한 대)

-12 (9/EL) XL

Data Received: 10/25/90

(lov/med) IT

Date Analysed: 10/29/90

t Moleture: not dec. _

Ellution Feeter: 1.2

(Pack/Cap) PACK azules

CONCENTRATION UNITS:


(ug/L or ug/Kq) UG/L

Number TICS found: .

CAS NUMBER

:: 2:

EST. COME. 27 CENTROTHE NAME 10.10 17.80



1/87 Re

657 728 45: FERNALD HOU 14 178 11:22 := 7 2937-451 FEEDEL **- 00077** ZPA SAMPLE N VOLATILE CREAKIES ANALYSIS CATA SHEET VELKEL Lab Name: TTRS-OAK RIDGE Contract: ADV SAS No.: UR WE'S Lab Cade: :---Case No.: 15151 SDG No.: 99402 Lab Sample In: Matrix: (spil/water) WATTO YEE1029 Lab File ID: *** (g/ml) ET Sammia WE/Wel: V381029 Data Received: (lev/med) Moisture: not dec. Date Analysed: 13/29/90 Dilution Factor: 1.0 (pack/cap) FACT :Caluar: CONCESTRATION UNITS: (ug/L or ug/Rg) UG/L Q COUPOUND CAS NO. U 74-87-3--Chloresethane 10 8 -Arczozathane 74-63-9---Albai cricerde 75-01-4-Chieroethane 10 U 75-00-3-Methylene Ciloride 10 75-09-2-J 3 -Acetone Carpon Diaulfice U 75-15-0-U -1.1-Dichlarcethene 75-35-4--1,1-01chloroethane ŭ 75-34-3--1,2-Dichlersethene (total) Ū 340-59-0 IJ 47-44-3---Chieroters. -1,2-Dichlorcethane U 107-06-2-30 2 78-93-3--4-BUELDORS -1,1,1-Trichloresthans 5 *:.-*71-55-4-5 U Carpon Tetrachioride 56-23-5---ATEAT YCEARS U 108-05-4-10 - Aresetichieresethane 75-27-4---1,2-01chleroprovene U 78-47-5--U 10061-01-5eis-1,1-Dichleropropene U 79-01-4--Trichlorosthene U Olbrosochierosethane 124-44-1-8 1.1.3-Trichlorosthane 79-00-6--71-43-2--tensene 90 5 Trans-1,1-01chloropropene 10061-02-4 -transfers 75-25-2--UJ 13 4-Methyl-2-Pentanone 102-10-1-3555 -1-lexamene 591-78-0-U Tetrachioresthene 127-15-4-9 -1,1,2,2-Tetrachloroethane 79-34-5---Toluene 108-68-3-Ü Chicropensene 108-90-7-U

TORK I VOL

-Ethylbensene

-dtyrene -Total Tylanes

100-41-4-100-42-5-

1330-20-7-

1/87 Re

657 229

us: FERRALI - 59 14 190 11:41

:::-15-50 S:2294 :

THE PARTY OF THE P

. 00078

VOLUNTILE CREAMICS AMALYSIS CATA SHEET THERETYELY IDENTIFIED COMPOUNDS

EFA SAMPLE HC

LAD MARGE TRE-OAK NICE

(pack/cap) PACK

Case No.: 18181 SAS No.: HB ...

CONTRACT: ADT

TRIKEL

8DG No.: 99402_

Lab Cade: -----

Lab Sample ID: 7381029

HETTIX: (SOLL/VETER) WATER

tab fila IC:

Sample we/vol:

THE BUILT THE COL

Date Received:

(low/med) icy PAAAT:

Cate Analysed: 13/29/90


Noissure: not dec. ____

Dilution Pactor: 1.3

Number TICE found: _

CONCENTRATION UNITS: (ug/L or ug/xg) EG/1

zar. coxc. RI בשענא מאססטום אשענ CAS NOOTE



FORK I YOA-TIC

1/87 Res

378 F94

PESTICITE ORGANICS ANALYSIS DATA SHEET EDA SAMPLE NO PRIZI CONTRACT: FERNALD LAD NAME: ITAS-KNOXVIII Case No.: 36377 SAR No.: MA SDG No.: 99403_ Lab Code: TT-MTL Lab Sample ID: 02034 MATTER: (SOIL/WHEET) WATER Lab Pila ID: 1000 (g/ml) ML Sample Wc/Vol: MA Data Received: (low/mad) LOW Lavel: Date Extracted: 11/16/90 dec. t Moisturs: not dec. ___ Date Analyzed: 11/19/90 SEPT (Sepf/Cont/Senc) Presertion: Dilution Paster: 1.0 PH: NO GFC Clashup: (Y/N) N CONCENTRATION UNITS: Q (ug/L or ug/Kg) UG/L COMPOUND CLE NO. 0 >05010 elpha-BEC 0.050IT 119-84-6--DETA-ARC 0.05010 319-85-7deltz-BEC 0.050IU GERRA-SEC (Lincane) 319-86-8--0.05010 58-69-9inpesoniar 0.05010 76-44-8-0.05010 Aldrin 109-00-2iopticalor spoxide 0.05010 024-67-3-Presultan I 0.1010 959-98-6-Oleldri. 60-57-1---4.4/-002 0.1010 72-55-9-Endrin 0.10IU 72-20-8--andosulfan ... 0.1010 33212-65-9-4.4'-000 72-54-8--Rndosulfan sulface ,031-07-8--4.4/-DDT 0.50IU 10-29-3---Hethoxycolor 0.1010 2-43-5-ENGILE KATORS 53494-70-5 alpha-chlordane 0.50IT 5103-71-9gamma-Chicronne 1.010 5103-74-2-4 0.5010 Foxabnene 8001-35-2--Arcelor-1016 0.50IT 12574-11-2-AFOGLOF-1221 0.5010 -AFOCLOT-1232 0.5010 1141-16-5 AFOCIOT-1242 0.5010 53469-21-9 AFOOLOF-1248 .1.010 2572-29-6-AFOOLOT-1254 1.010 11097-69-1-AFOCIOT-1260

FORM I PEST

المتجوب

1/87 Re

PESTICIE ORGANICS ANALYSIS DATA SE	EPA (MPLZ
	. 0046	3
ab Name: Tig-KNOX/	: FERNALE	30403
Case No.: 38377 SAB No.	: <u>MA</u>	7790-
ATTIN: (SOLL/WEEGE: WATER	THE SEMPLE 13. FIAS	33
1000 (g/mL) ML	TAB File ID:	
evel: (lev/med) :OH	Date Received: 11/0	
Maisents: sat dag dag	Date Extracted: 11/1	
xtraction: (Sepf/Cont/Sone; SEPF	Date Analysed: 11/1	
2 Classes (Y/N) N pm: 6.0	Dilucion Factor: 1.0	
(Class () -	MIRRITA UNITS:	
CAR NO. CENTROCKE (UE/I	or ug/Rg) <u>UG/L</u>	<u> </u>
319-64-6	0.0501	- (
319-64-6	0.0501	
119-66-6	0.0501	
319-86-8	: 0.0501	= 1
76-44-6	0.0501	
		ם ו
1024-57-3	0.0501	ਹ ;
1024-57-3	0.101	U
	0.101	บ - ¦
·	0.101	נ ו
72-10-6	0.101	
·	0.131	T j
72-54-6		T i
	: 0.101	
50-29-3	0.501	:
72-41-5	0.181	
72-41-5 53494-70-5	0.501	U
53494-70-5	0.501	נו !
	1.01	T I
	0.501	
	0.501	
	0.501	
11141-16-6		- 1
53469-21-9Arocior-1242		
53469-21-9	* · · ·	
		Ū.
11097-69-1 11096-62-5		1
· · · · · · · · · · · · · · · · · · ·		

FORM I FEST

1/87 Re

121 -21-46 121252# :

T44 F12 -78977-451 FERNALD

EPA SAMPLE NO SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET SBLKBZ Contract: ACT Lab Name: TAS-OAK RIDGE SDG No.: 99403 SAS NO.: MA Case No.: 15377 Lab Code: ----02031 Lab Sample ID: Matrix: (soil/water) WATTE 02221E Lab File ID: 1000 (g/mL) MT Sample wt/vol: Date Received: WC: (10W/mem; Date Extracted: 11/15/90 Level: dec. t Moisture: not dec. _ Date Analyzed: 1:/19/90 SEPE (Sepf/Cont/Sonc) Cilution Factor: 112 EXTIRCTION: p#: _ K(K/K) CONCENTRATION UNITS: GPC Cleanup: Q (ug/L or ug/Kg) UG/L COMPOUND **ಜ** ೫೦. U 50 99-09-2----3-Nitroaniline U 10 83-32-9----Acenaphthene U 50 51-28-5-----2,4-Dinitropnenol U 50 u 10 132-64-9-----Dibenzofuran ı 10 121-14-2-----2,4-Dinit=Stoluene 10 U 84-66-2------Olechylphthalate U 10 U 10 86-73-7----Fluorene 50 l U U 50 534-52-1-----4,6-Dinitro-3-Metnylphenoi 10 U 177 U 10 119-74-1----Hexachloropenzene U 50 87-86-5-----Pentachlorophenol U 10 10 U 120-12-7----Anthracene U 10 84-74-2-----Di-n-Butylphthalats 10 206-44-0-----Fluorantmene l tr 10 10 រៃ 🗗 85-68-7-----Butylbenzylphthalace U 20 91-94-1----3,3'-Dichloropenzidine lu 10 56-55-3-----Benzo(a) Anthrzcane 10 10 u 218-01-9----Chrysene 10 117-81-7-----ois(2-Ethylnexyl) Phthalate U 10 10 111 205-99-2-----Benzo(b) Fluoranthene U 13 207-08-9----Benzo(k)Fluoranthene 10 U שו 50-32-8----Benzo(a) Pyrene 10 193-39-5----- Indano(1.2,3-cd) Pyrane U 10 53-70-3-----Oibenz(a,h)Anthracene 191-24-2-----Benzo(g,n.i) Perylene

(1) - Cannot be separated from Diphenylamine

744 P11 15937-61 FEMALE

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET 13

EPA SAMPLE NO

Q

SBLKB2

Contract: AET Lab Name: TTAS-OAK FITGE SEG No.: 99403 Case No.: 15177 SAS No.: NA

Lab Code: ------02021 Lab Sample ID: Matrix: (soil/water) WATER

can file ID: 1000 (g/mL) HL Sample wc/vol:

Data Recelved: (low/med) TOW Date Extracted: 11/15/90 Level:

dec. t Moisture: not dec. _ 1/19/90 Date Analyzed:

SEPF (Sepf/Cont/Sonc) Cilution Factor: 1.0 Extraction: pH: _

(X/H) 7 CONCENTRATION UNITS: GPC Cleanup: (ug/L or ug/Kg) UG/ COMPOUND

CAS NO. ıσ 10 .10 111-44-4-----bis(2-Chlorosthyl)Ether U 10 95-57-8----2-Chloropnenol U 10 541-73-1----1,3-Dichloropenzene U 10 106-46-7----i,4-Dichloropenzene U 10 -----Benzyl Alcohol IJ 10 95-50-1-----1,2-Dichloropenzene U 10 10 U 10 U 10 U 10 67-72-1----Hexachloroethane : " 10 U 10 10 ---- Isophorone U 10 -- 3-X1cropnenor -2,4-Dimetnyiphenol U 88-75-5-50 105-67-9----U -- Benzoic Acid 10 -bis(2-Chloroethoxy) Methane 10 U 65-85-0--2,4-Dichloropnenol 111-91-1---ij 10 ----1,2,4-Trichloropenzene 120-63-2-10 IJ 120-82-1---10 -нарпспаделе 91-20-3--U -----Chloroaniline 10 ---Hexachloroputadiene ับ 106-47-8--10 59-50-7----4-Chloro-3-Methylphenol 10 ----2-Metnylnaphthalene IJ 10 77-47-4-----Hexachlorocyclopentaciene U 38-06-2----2,4,6-Trichlorophenol ij 50 95-95-4----2,4,5-Trichloropnenoi U 1 ---- 2-Chloronaphenalene 51 IJ 91-58-7----2-Nitroaniline 1. 131-11-3-----Dimetnyl Phthalate U ני 208-96-8----Acenaphthylene

744 F18 **2735-**0. -287-44

•••	EPA SAMPLE NO
10 SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET	SBLXB1
Contract: ADY	
Lab Name: ITAS-OAK FINGE CONTINUE: ADDITION OF THE SAME SDG	No.: 99403
	32007
Matrix: (soil/water) WATER	
Sample wt/vol: 1000 (9/mi) ha	
Lavel: (low/med) LOW Date Extracted	: 11/05/90
t Moisture: not dec dec	
Extraction: (Sepf/Cont/Sone;	
GFC Cleanup: 1/3/ CONCENTRATION UNITS:	
CAS NO. COMPOUND (ug/L or ug/kg) UG/L	
99-09-2	20 00 00 00 00 00 00 00 00 00 00 00 00 0
193-39-5Dibenz(a,h)Anthracene 52-70-3Benzo(g,h,i)Perylene 191-24-2	10

EPA SAMPLE N SEMINOLATILE ORGANICS ANALYSIS DATA SHEET SBLÄBL Contract: ADV Lan Name: ITAS-OAK RINGE SDG No.: 99403 Lab Code: T-MT. Case No.: 3637 SAS No.: NA Lab Sample ID: 02007 Matrix: (soil/water) WATER Lab File II: 02007 1000 (g/mL) ML Sample we/vol: Date Received: Level: (low/med) LOW Date Extracted: 11/05/90 dec. __ % Moisture: not dec. ____ Date Analyzed: ::/:9/90 Extraction: (Sepf/Cont/Sonc) SEPE Cilucion Factor: 1.0 GPC Cleanup: (Y/N) N pH: ___ CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L COMPOUND **ಾ**ತ ೫೦.

ಾ ತ ೫೦.	CG C		1
		10	U
	phenolbis(2-Chlorostnyl)Ether	10	10
108-95-2		10	U
111-44-4		10	ם
24-17-8	bis(2-Chloroethy1)Edis- 2-Chlorophenol	10	U
95-5/-0	1, J-D1Ch1Grobenson	10	io
541-/3-1	1,4-Dichloropenzene	10	u
106-46-7-	Benzyl Alcohol		Ü
100-51-6	i.2-Dichloropenzene	10	Ü
95-50-1	- Mernylphenol	10	, -
95-48-7	13(2-Chloroisopropy)	10	U
103-60-1	-Mechylphenol	10	U
106-44-5		10	U
671-64-7		10	ļ C
67-72-1	H-Nitroso-Di-n-PropylatingHexachlorostnaneNitropensene	10	U
00-05-3		10	U
90-95 3	Nitropensene	10	10
		50	ש
88-/3-3-	4-Dimethy iphones	10	ū
		10	u
65-85-0			lu
111-91-1	2.4-Dichlorophenol	10	iu
120-83-2-	2.4-Oichlorophenol	10	ŭ
120-82-1-		10	1 -
91-20-3	-1,2,4-Trichlorobenzane	10	U
		10	U
: 87-68-3	Hexachlorobutadiane 4-chloro-3-Methylphenoi	10	! U
59-50-7	- Methylnaphthalene	10	U
		10	្រុ
		50	U
		10	1
95-45-4	2.4,6-Trichlorophenol	50	
01-58-7		10	
95-74-4	2-Chioronaphthalene 2-Nitroaniline 2-Nitroaniline 3-Dimethyl Phthalate 3-Acenaphthylene 3-6-Dimitrotoluene	10	
	Dimethyl Future	. 10	U
			!
208-20-6	6-Diniesocolum		

: =

1.00 31 198 12.08 48; FEENALD 12:1284 1 EBNT 511:17 7098 684 1 11:1884 1 744 PG7 35939-43: TEMPLO

EPA SAMPLE NO SEMIVOLATILE CRGANICS ANALYSIS DATA SHEET 99403R Contract: ADV Lap Name: ITAS-OAK RIDGE SDG No.: 99403 SAS NO.: NA Case No.: 35777 Lab Code: --- wwt Lab Sample II: Matrix: (soil/water) WATER FF7447R Lab File ID: (g/BL) ML 1000 Sample wt/vol: 11/01/90 Date Received: LOW_ (low/med) Lavel: Data Extracted: 11715/90 dec. t Moisture: not dec. ___ 11/19/90 Date Analyzed: SEPE (SepF/Cont/Sonc; Extraction: Dilution Factor: 1.0 **-**#: GPC Cleanup: (Y/H) Y CONCENTRATION UNITS: Q (ug/L or ug/Kg) UG/L COMPOUND CAS NO. ס 50 99-09-2----3-Nitroaniline U 10 83-32-9-----Acanaparhene 50 51-28-5------2,4-Dinitropnenci U 50 100-02-7----4-Nitropnenol U 10 132-64-9------------Dibenzofuran U 10 U 10 84-66-2-----Disthylphtmalate U 10 i u 10 U 50 50 lu 534-52-1-----4,6-Dinitro-2-Metnyipnenoi u 10 U 10 101-55-3-------------Bromopnenyi-phenyietner U 10 118-74-1----Hexachloropenzene ! U 50 37-86-5-----Pentacnloropnenoi U 10 85-01-6------Phenanchrene U 10 120-12-7-----Anthracene tT 10 10 206-44-0-----Fluoranthens U 10 U 10 20 U 91-94-1-----3,3'-Dichloropenzidine U 10 56-55-3-----Benzo(a) Anthracene U 10 218-01-9------Chrysene U 10 117-61-7-----ois(2-Ethylnexy1) Phthalate ט 10 17-84-0------Di-n-Octyl Phthalate 10 10 205-99-2----Benzo(b) Fluoranthene U 10 207-08-9-----Genzo(k) Fluoranthene IJ 10 50-32-8------Benzo(a) Pyrene U 10 193-39-5-----Indeno(1,2,3-cd) Pyrene iu 10 53-70-3-----Olbenz(a,h) Anthracene U 191-24-2-----Benzo(g,h.i) Perylana (1) - Cannot se separated from Dipnenylamine تتج يحمله

---2,6-Dinitrotoluene

42

606-20-2--

744 904 ASI FERNALD 22939-1051 FERMALD VOU 21 198 12:26 :11-21-90 :2:26 77 : BENE SALL COSS CLOT EPA SAMPLE NO. SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET 99403 Contract: ADV Lab Name: TTAS-OAK EITGE SDG No.: 99403 Case No.: 2527- SAS No.: NA Las Code: TT-WT Lab Sample ID: FF7553 Matrix: (soil/water) WATER FF2552 Lab File ID: 500 (9/mL) ML Sample wt/vol: 11/01/90 Date Received: (low/med) LOW Date Extracted: 11/05/90 Level: dec. _ 1 Moisture: not dec. Date Analyzed: 11/19/90 SEPE (Sepf/Cont/Sono: Extraction: Cilution Factor: 110 pH: (A/H) A-SPC Cleanup: CONCENTRATION UNITS: (ug/L or ug/Kg) UG/I 3 COMPOUND CAS NO. U 100 99-09-2-----3-Nitroaniline U 20 83-32-9-----Acenapathene 10 100 ______2, 4-Dinitrophenoi U 100 51-28-5---100-02-7----4-Witropnenol 20 IJ U 20 121-14-2-----2,4-Dinitrotcluene : 3 20 84-66-2-----Dietnylphtmalate 111 20 7005-72-3-------Chlorspnenyl-pnenyletner ij 20 36-73-7----Fluorane IJ 100 100-01-6------IJ 100 534-52-1----4,6-Dimitro-2-Metnyipmenoi 20 : 😲 20 101-55-3----4-Bromopnenyi-pnenyletner ij 20 115-74-1------nexacnloromenzene : **"** 100 87-96-5-----Pentachlorophenol iu 20 85-01-6----Phenanthiane ! U 20 170-12-7-----Anthracene U 20 17 20 206-44-0----Fluorantnene : ប 20 1 77 20 85-68-7-----Butylbenzyiphthalate ! U 40 91-94-1----3,21-Dichloropenzidine 13 20 56-55-3------Benzo(a) Anthracene_ U 20 118-01-9------Chrysone : ប 20 20 itt 20 105-99-2-----Benzo(b) Fluoranthene ! " 20 207-08-9----Benzo(X) Fluoranthene 20 10 50-32-8-----Benzo(a) Pyrene iu 20 23-39-5-----Indeno(1,2,3-cd) Pyrene 10 20 -----Olbenz(a.m) Anthracene 20 191-24-2------Genzo(q,n,1) Perylene (1) - Cannot be separated from Diphenylamine

٠.,

EPA SAMPLE NO. SEMIVOLATILE GROWNICS ANALYSIS DATA SHEET 99403 Lab Name: ITAS-OAK RIDGE Contract: ADV Lab Code: ___WE_ Case No.: 15177 SAS No.: NA SDG No.: 99407 Lab Sample ID: FF7552 Matrix: (scil/water) WATTE FF7EE2 Lab File ID: 500 (g/mL) WY Sample wt/vol: Date Received: 11/01/90 Level: (low/med) LOW Date Extracted: 11/05/90 i Moisture: not dec. ____ dec. _ Date Analyzed: 11/19/90 Extraction: (SepF/Cont/Sone: SEPF Dilution Factor: 1.0 GFC Cleanup: (Y/N) P pH: ____ CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L CAS NO. COMPOUND

		1
108-95-2Phenol	20	la l
108-95-2bis(2-Chloroethyl)Ether		U
95-57-82-Chloropnenol	20	u
541-73-11,J-Dichlorobenzene	20	i U
:05-46-7i,4-Dichlorobenzene	. 20	U
106-46-7	20	i i
	20	U
	20	U !
95-48-72-Methylphenol	20	U
108-40-1	20	U
	20	u ·
67:4-7	• • • • • • • • • • • • • • • • • • • •	iu i
67-12-1Hexachlorosthane	20	ŭ
98-95-3Nitropenzene	2.0	
TRANSPORTER	2 U	Ü
on the formation 2-Nitrophenoi	20	
105-57-6	20	
ce as-a-managic Acid	4	13
65-65-0	20	U
120-63-22,4-Dichloropnenol	20	ט
120-83-2-1	20	្រ
120-82-1	20	U
91-20-3Naphthalene	20	U
106-47-64-Chloroaniline	20	T
87-66-3Hexachlorosutadiene	20	ប
59-50-7	20	U
91-57-42-Metnyinaphthalene	23	. 🖰
77-47-4Hexacrlorccyclopentaglane	20	i U
88-06-22,4,6-Trichlorophenoi	100	io
Of the state of th	20	u
o1-58-72-Chloronapatnatene	100	i i
28-74-42-N1TTOANLLING	20	ie !
121-11-3Dimetnyl Phthalate	20	Ü
201-26-3	20	i i
606-20-22,6-Dimizzacoluene	20	
000-20-2		<u> </u>

1/87 Re

ATTACHMENT B

FINAL ANALYTICAL RESULTS

K-65 DECANT SUMP TANK REMOVAL ACTION

Radiological Validation Qualifiers for OU4 (Revision 1) - 08/04/92

SAMPLE SUF	FIX RADIONUCLIDE	RESULTS	2-SIGMA	UNITS	Q 5
099411	CS-137	< 20		pCi/l	R
099411	NP-237	< 1.0		pCi/l	R
099411	PU-238	< 1.0		pCi/l	J
099411	PU-239/240	< 1.0		pci/l	-
099411	RA-226	836	± 118	pCi/l	R
	RA-228	< 3.0	5	pCi/l	R
099411		< 150		pCi/l	R
099411	RU-106	< 5.0		pCi/l	R
099411	SR-90			pCi/l	J
099411	TC-99	< 30.0			U
099411	TH-228	< 1.0		pCi/l	
099411	TH-230	< 1.0		pCi/l	R
099413	TH-232	< 1.0		pCi/l	-
099411	TH-TOTAL	< 7.1		vg/1	D
099411	U-235	1310	± 170	pCi/l	-
099411	U-238	26000	± 2800	pCi/l	-
	•	77400	± 11500	ug/1	J
099411	U-TOTAL	77400	- 11300	~3/ ~	•

- Radiological Validation Qualifiers for OU4 (Revision 1) - 08/04/92

SAMPLE SUF	FIX RADIONUCLIDE	RESULTS	2-SIGMA	UNITS	Q5
099412	CS-137	< 20		pCi/l	R
099412	NP-237	1.2	± 0.8	pCi/l	-
	PU-238	< 1.0		pCi/l	J
099412		< 1.0		pCi/1	-
099412	PU-239/240	1120	± 158	pCi/l	. J
099412	RA-226		_	pCi/l	J
099412	RA-228	4.81	± 1.11	•	R
099412	RU-106	< 150		pCi/l	
099412	SR-90	< 5.0		pCi/l	_
099412	TC-99	< 30.0		pCi/l	_
099412	0-235	1362	± 187	pCi/l	R
	บ-238	22490	± 4269	pCi/l	R
099412	•	75000	± 11400	ug/1	J
099412	U-TOTAL	13000	- 11100	-3, -	

SAMPLE S	UFFIX RADIONUCLIDE	RESULTS	2-SIGMA	UNITS	Q5
099415	CS-137	< 20		pCi/l	 ;
099415	NP-237	< 1.0		pCi/l	R
099415	PU-238	< 1.0		pCi/l	R
099415	PU-239/240	< 1.0	•	pCi/l	J
099415	RA-226	797	± 113	pCi/l	R
099415	RA-228	< 3.0		pCi/l	-
099415	RU-106	< 150		pCi/l	J
099415	SR-90	6.47	± 1.35	pCi/l	J
099415	TC-99	43.8	± 20.7	pCi/l	- 1
099415	TH-228	2.72	± 1.53	pCi/l	R
099415	TH-230	197	± 27	pCi/l	R
099415	TH-232	< 1.8	÷ 41	pCi/l	J
099415	TH-TOTAL	< 16		ug/1	J
099415	U-235	1074	± 111		- •
099415	· U-238	20390		pCi/l	J !
,			± 2110	pCi/l	J
099415	U-TOTAL	70400	± 11000	ug/l	R
l <u></u>					!

Radiological Validation Qualifiers for OU4 (Revision 1) - 08/04/92

SAMPL	SUFFIX	RADIONUCLIDE	RESULTS	2-SIGMA	UNITS	Q5
099416	<u> </u>	AC-227	< 91.1		pCi/l	
099416		PA-231	< 431		pCi/l	J
099416	•	PB-210	8660	± 866	pCi/l	J
099416	•	PO-210	7080	± 930	pCi/l	•
099416	•	RA-224 (GAMMA)	< 27		pCi/l	·J
099416		RA-226	1640	± 230	pCi/l	Ĵ
099416	•	RA-226 (GAMMA)	973	± 81	pCi/l	R
099416		RA-228	8.80	± 1.56	pCi/l	J
099416		RA-228 (GAMMA)	< 76		pCi/l	·DJ

Radiological Validation Qualifiers for OU4 (Revision 1) - 08/04/92

1	SAMPLE	SUFFIX RADIONUCLIDE	RESULTS	2-SIGMA	UNITS	Q5
ŀ	099417	AC-227	5783	± 603	pCi/q	J
١	099417	PA-231	< 855		pCi/g	DJ
1	099417	PB-210	123200	± 12330	pCi/g	J
İ	099417	RA-224	< 41		pCi/g	J
1	099417	RA-226	128500	± 6440	pCi/g	Ĵ
ļ	099417	RA-228	< 140		pCi/g	DJ
Ĺ	099417	TH-230	52130	± 7582	pCi/g	J
İ	099417	U-TOTAL	< 1255	_ 100_	ug/g	DJ

Radiological Validation Qualifiers for OU4 (Revision 1) - 08/04/92

SAMPLE	SUITIX RADIONUCLIDE	RESULTS	2-SIGMA	UNITS	Ω5
099420	AC-227	< 2.2		pCi/l	
099420	PA-231	< 506	•	pCi/l	. DJ
099420	PB-210	2650	± 270	pCi/l	J
099420	PO-210	2490	± 350	pCi/l	J
099420	RA-224	< 33		pCi/l	J
099420	RA-226	481.0	± 68.0	pCi/l	J
	RA-226 (GAMMA)	782	± 72	pCi/l	J
099420		< 3.0		pCi/l	J
099420	RA-228			pCi/l	DJ
099420	RA-228 (GAMMA)	< 57			
099420	TH-228	< 2.4		pCi/l	DJ
099420	TH-230	16.5	± 4.3	pCi/l	J
099420	TH-232	< 1.0		pCi/l	-
099420	TH-TOTAL	< 5.3		ug/l	D

a completely

ATTACHMENT C

POTENTIAL ARARS

K-65 DECANT SUMP TANK REMOVAL ACTION

POTENTIAL ARARS

50

K-65 DECANT SUMP TANK REMOVAL ACTION

Chemical, Location, or Action	Citation	ARAR/TBC	Rationale for Implementation	Compliance Strategy
Radionuclide Emmissions (except Radon)	40 CFR 61, Subpart H Emissions of radionuclides to the ambient air from DOE facilities shall not exceed those amounts that would cause any member of the public to receive in any year an effective dose equivalent of 10 mrem/yr.	Applicable	Plant 8 stack (equipped with a continous sampler) could contribute to to the dose to members of the public from the air pathway (NESHAPS).	NESHAP compliance for Plant 8 stack is documented in the FMPC sitewide U.S. EPA approved NESHAP document.
	10 CFR 20.101-105 Radiation doses, levels and concentrations for restricted and unrestricted areas shall not exceed specified limits.	Relevant and Appropriate	Radioactive materials from this Removal Action could contribute radiation doses, levels, and concentrations to individuals in restricted and unrestricted areas, which could exceed the specified limits.	Protective measures will be implemented in accordance with the task specific Health and Safety Plan for the K-65 Decant Sump Tank Removal Action.
Treatment, Storage, and Handling	40 CFR 264, General Standards •40 CFR 264.13 (Waste Analysis) - Operators of a facility must obtain a detail chemical and physical analysi of a representative sample of each hazardous waste to be treated, stored, or disposed of at the facility prior to treatment, storage, or dispose	s	The liquid removed from the K-65 decant sump tank must be handled, stored, and inspected with the liquid removed being managed as a hazardous waste.	As outlined in the Removal Action Work Plan, samples will be taken prior to the liquid being transferred to the tanks in Plant 2/3. Samples will analyzed for HSLs.

POTENTIAL ARARS

K-65 DECANT SUMP TANK REMOVAL ACTION

Chemical,				
Location,			Rationale for	Compliance
or Action	Citation	ARAR/TBC	Implementation	Strategy

•40 CFR 264.14 (Security) Relevant and operators of a facility must Appropriate prevent the unknowing or unauthorized entry of persons or livestock into the active portion of the facility, maintain a 24-hour surveillance system, or surround the facility with a controlled access barrier and maintain appropriate warning signs at facility approaches.

•40 CFR 264.15 (Inspections) Relevant and Operators of a facility must Appropriate develop a schedule and regularly inspect monitoring equipment, safety and emergency equipment, security devices and operating and structural equipment that are important to preventing, detecting or responding to environmental or human health hazards, promptly or immediately remedy defects, and maintain an inspection log.

In addition to the FMPC sitewide security measures, the specific access control measures for the K-65 Decant Sump Tank Removal Action are outlined in the task specific Health and Safety Plan, section 6.1.

Inspections of Plant 2/3 storage area and the FMPC water treatment facilities will be in accordance with the FMPC Waste Management Plan, the Waste Analysis Plan, and Standard Operating Procedures.

POTENTIAL ARARS

S)	K-65 DECAN	T SUMP TANK RE	MOVAL ACT	ION	
Chemical, Location, or Action	Citation	ARAR/TBC	_	tionale for plementation	Compliance Strategy
	•40 CFR 264.16 (Training) Operator must train personnel within 6 months of their assuming duties at a facility in hazardous waste management procedures relevant to their positions including emergency response training.				All FMPC personnel are trained in accordance with 29 CFR 1910.120. Personnel involved with this Removal Action will be trained on the applicable operating procedures and K-65 Emergency Procedure.
Discharge of Treatment System Effluen	40 CFR 122.41 (i) OAC 3745-33-05 It Monitoring requirements Discharges must be monitored to assure complianc Discharges will be monitored for: -the mass of each pollut -the volume of each poll -frequency of discharge measurements as appropri	ant utant and other	di th as th li wi	equired of all direct scharges to waters of the U.S The effluent a result of the etreatment of the equid removed all be discharged to be Great Miami River.	Effluent from the treatment of liquid removed from the K-65 decant sump tank will be monitored according to the requirements in the FMPC NPDES permit.
	Approved test methods must be followed for waste constituento be monitored. Detailed requirements for analytical procedures and quality controlare provided.	its			Same as above.

POTENTIAL ARARS

K-65 DECANT SUMP TANK REMOVAL ACTION

Chemical, Location, or Action	Citation	ARAR/TBC	Rationale for Implementation	Compliance Strategy
	40 CFR 136.1-136.4 (Cont'd)			
	Sample preservation procedure container materials, and max allowable holding times are prescribed.			
	40 CFR 122.41 (i)	Applicable		Same as above
	Comply with additional substantive conditions such	as:		
	-Duty to mitigate any advers effect of any discharge; and			
	-Proper operation and maintenance of treatment systems.			
Chemicals in Drinking water	emicals in 40 CFR 141.12 inking water The following MCLs for organic chemicals are the the maximum levels of a contaminant in water which is delivered to a free flowing outlet of the ultimate user of a public water system: - Chloroform 0.1 mg/l - Ethyl-benzene 0.7 mg/l*		The requirement is not applicable since no public water system is involved. It is relevant and appropriate to protect drinking water from the contaminants listed. These contaminants may mitigate or leach into the underlying aquifer.	at Plant 8 which was installed as part of the Consent Agreement Removal No. 1.
. 11	-Pentachlorophenol 0.2 mg/l -PCBs 0.0005 m -Tetrachloroehtylene0.005 mg	ıg/1*		4 4 8

び! こご

POTENTIAL ARARS

K-65 DECANT SUMP TANK REMOVAL ACTION

		il.		
Chemical, Location, or Action	Citation	ARAR/TBC	Rationale for Implementation	Compliance Strategy
Chemicals in Drinking Water	40 CFR 141.12 (Cont'd) -Toluene 2.0 mg/l* -Trichloroethylene 0.005 mg/ -1,1,1 Trihloroethane.2 mg/l -Xylene 10.0 mg/l *Proposed	*		
Radiation Dose Limit (Drinking Water pathway)	DOE Order 5400.5, Chapter II, Section 1.a The exposure of members of the public to radiation sources as a consequence of all routine DOE activities shall not cause, in a year, an effective dose equivalent greater than 100 mrem from all exposure pathways.	To Be Considered	The radioactive constituents of the liquid removed from the decant sump tank could contribute to the dose to members of the public from drinking water.	The DCGs established by the referenced DOE Order can not be met with the current FMPC available waste water treatment facilities. The established DCGs will be attained when the AWWT is operational in 1993.

ATTACHMENT D

FEMP ADMINISTRATIVE RECORD INDEX
K-65 DECANT SUMP TANK REMOVAL ACTION

ටැ ග

FEMP ADMINISTRATIVE RECORD REMOVAL ACTION #9 -- DECANT SUMP TANK

xdex Number	Document Number	Document little	Rev.	Document	from 1o	# of <u>Pages</u>	Type of Document	Location <u>Number</u>
014-101.1	NMCO:EMT:90-539	REMOVAL SITE EVALUATION ON THE K-65 DECANT SUMP TANK WATER		08/17/90	WMCO DOE-FMPC	8	REPORT	RA #9 FILE
014-101.3		POTENTIAL ARARS K-65 DECANT SUMP TANK REMOVAL ACTION	0	/ /		5	ENCLOSURE	RA #9 FILE
014-205.1	DOE - 1784 - 90	REMOVAL ACTION MEMORANDUM: K-65 DECANT SUMP TANK		08/23/90	DOE-FMPC	2	LEITER	RA #9 FILE
014-207.1		K-65 DECANT SUMP TANK REMOVAL ACTION WORK PLAN FEED MATERIALS PRODUCTION CENTER	D	09/01/90	WMCO DOE-ORO	45	WORK PLAN	RA #9 FILE
-014-207.2		K-65 DECANT SUMP TANK REMOVAL ACTION WORK PLAN FEED MATERIALS PRODUCTION CENTER SEPTEMBER 1990		09/01/90	HMCO DOE-ORO	49	WORK PLAN	RA#9 FILE
2-014-2 07. 3		K-65 DECANT SUMP TANK REMOVAL ACTION WORK PLAN FEED MATERIALS PRODUCTION CENTER DECEMBER 1990		12/01/90	UMCO DOE-ORO	100	WORK PLAN	RA #9 FILE
1-014-207.4		UMCO TECHNICAL RECOMMENDATIONS FOR THE RESPONSE TO U.S. EPA MODIFICATIONS OF THE K-65 DECANT SUMP TANK REMOVAL ACTION WORK PLAN	0	/ /		7	ENCLOSURE	RA #9 FILE
R-014-207.5	DOE - 867 - 91	K-65 DECANT SUMP TANK REMOVAL ACTION	0	03/01/91	DOE - FMPC USEPA	2	LETTER	RA #9 FILE
R-014-207.6	DOE - 76-91	K-65 DECANT SUMP TANK REMOVAL ACTION WORK PLAN		10/17/90	DOE-FSO EPA	2	LETTER	RA #9 FILE

FEMP ADMINISTRATIVE RECORD REMOVAL ACTION #9 -- DECANT SUMP TANK

Index Number	<u>Document Number</u>	Document Title	Rev.	Document	from To	# of Pages	Type of Document	Location Number
R-014-1001.1		K-65 DECANT SUMP REMOVAL		04/01/91	OEPA DOE-FMPC	1	LETTER	RA #9 FILE
R-014-1001.2		REMOVAL #5 - DECANT TANK U.S. DOE FERNALD OH6 890 008 976	0	01/10/91	USEPA DOE-FMPC	, 2	LETTER	RA #9 FILE
R-014-1001.3		COMMENTS K-65 DECANT SUMP TANK REMOVAL W.P.		11/19/90	OEPA DOE-FMPC	1	LETTER	RA #9 FILE
R-014-1001_4		CONDITIONAL APPROVAL K-65 DECANT SUMP REMOVAL WORK PLAN		01/11/91	OEPA DOE-FMPC	2	LETTER	RA #9 FILE
R-014-1001.5		REMOVAL #5 K-65 DECANT TANK U.S. DOE FERNALD OH6 890 QOB 976		11/13/90	USEPA DOE-FMPC	4	LETTER	RA #9 FILE
R-014-1003.1		THE USDOE ANNOUNCES THE AVAILABILITY FOR PUBLIC REVIEW OF THE ADMINISTRATIVE RECORD FILE FOR THE K-65 DECANT SUMP TANK REMOVAL ACTION AT THE DOE FMPC AT FERNALD, OH		/ /		1	ATTACHMENT	RA #9 FILE
R-014-1007.1		RESPONSE TO THE U.S. EPA COMMENTS K-65 DECANT SUMP TANK REMOVAL ACTION WORK PLAN		12/11/90	DOE-FMPC USEPA	8	REPORT	RA #9 FILE
R-014-1007.2		RESPONSE TO OHIO EPA COMMENTS K-65 DECANT SUMP TANK REMOVAL ACTION WORK PLAN		12/11/90	DOE-FMPC OEPA	2	REPORT	RA #9 FILE
R-014-1007.3	·	THE RESPONSE TO OHIO EPA GENERAL COMMENTS ON THE K-65 DECANT SUMP TANK REMOVAL ACTION WORK PLAN		/ /	,	2	LETTER	RA #9 FILE